

ADDENDUM NO. 1
ICE RINK RESURFACING PROJECT
2023

1. Under Section 1. Scope –

Delete the Base Bid Paragraph and **Replace** with

“Base Bid - The Contractor shall remove the existing asphalt, and then add 2” inches of new hot mix Type 7 top course asphalt. The Contractor may keep the millings, otherwise dispose of the millings on City property at the location specified by the City DPW.