

ADDENDUM NO. 3  
ICE RINK RESURFACING PROJECT  
2023

1. Under Section 1. Scope –

**Delete** the 2<sup>nd</sup> paragraph, Base Bid, and **Replace** with the following new paragraph,

Base Bid – The Contractor shall clean all asphalt, mill existing asphalt and crack fill where needed. Add shim coat as needed to make true and level. Add tack coat and Pave with 1.5” of new hot mix Type 7 top course asphalt.

The slope of the approximate 2 – 3 ft wide outside ring of asphalt near the boards shall remain the same. Final slope of interior area shall be between 1 to 2 percent to center drain.

The Contractor may keep the millings if desired, otherwise, the Contractor may dispose of the millings on City property at the location specified by the City DPW.

2. Under Section 1. Scope –

**Delete** Bid Alternate.

CITY OF NORWICH, DEPARTMENT OF PUBLIC WORKS  
ONE CITY PLAZA  
NORWICH, NEW YORK

Phone 607-334-1255  
Fax 607-334-1254